

Summary Report

Project:MIXED USE DEVELOPMENT
Project Location:9000, No.3 Road, RICHMOND, BC
Project Type: Residential Project
Scope of Work:Metal Stud, Insulation & Drywall

Steel Fraimg

Material	Height	Pieces	Units	Unit Price per (LF)		Total
103mm (4") bottom steel track 25ga	10	51	Pieces	\$ 0.80	\$	407.08
103mm (4") slotted top steel track 25ga	10	51	Pieces	\$ 1.03	\$	525.10
103mm (4") steel stud 25ga	13	209	Pieces	\$ 0.85	\$	2,306.46
103mm (4") steel stud 25ga	10	162	Pieces	\$ 0.85	\$	1,375.22
152mm (6") bottom steel track 18ga	10	28	Pieces	\$ 1.97	\$	551.32
152mm (6") slotted top steel track 18ga	10	28	Pieces	\$ 4.02	\$	1,126.44
152mm (6") steel stud 18ga	13	10	Pieces	\$ 2.31	\$	300.17
152mm (6") steel stud 18ga	5	163	Pieces	\$ 2.31	\$	1,881.84
152mm (6") steel stud 18ga	10	20	Pieces	\$ 2.31	\$	461.80
64mm (2 1/2") bottom steel track 25 ga bulkhead	10	219	Pieces	\$ 0.88	\$	1,920.63
64mm (2 1/2") J track 25ga	10	15	Pieces	\$ 0.66	\$	99.15
64mm (2 1/2") Shaftwall CH Stud 20GA	13	7	Pieces	\$ 2.62	\$	238.60
64mm (2 1/2") Shaftwall CH Stud 20GA	10	3	Pieces	\$ 2.62	\$	78.66
64mm (2 1/2") Shaftwall CH Stud 20GA	9	65	Pieces	\$ 2.62	\$	1,533.87
64mm (2 1/2") Shaftwall CH Stud 20GA	5	24	Pieces	\$ 2.62	\$	314.64
64mm (2 1/2") slotted top steel track 25 ga bulkhead	10	219	Pieces	\$ 0.69	\$	1,504.53
64mm (2 1/2") slotted top steel track 25ga	10	15	Pieces	\$ 0.69	\$	103.05
64mm (2 1/2") steel stud 25 ga bulkhead	1	1640	Pieces	\$ 0.55	\$	902.00
64mm (2 1/2") steel stud 25 ga Ceiling Joist	10	1184	Pieces	\$ 0.55	\$	6,510.74
64mm (2 1/2") steel track 25 ga Wall Track	10	1249	Pieces	\$ 0.88	\$	10,950.75
92mm (3 5/8") bottom steel track 18ga	10	1	Pieces	\$ 1.38	\$	13.78
92mm (3 5/8") slotted top steel track 18ga	10	1	Pieces	\$ 3.38	\$	33.82
92mm (3 5/8") steel stud 18ga	13	2	Pieces	\$ 1.74	\$	45.16
carrying channel 1-1/2"	12	120	Pieces	\$ 0.77	\$	1,113.12
carrying channel 1-1/2"	12	34	Pieces	\$ 0.77	\$	315.38
carrying channel 3/4"	12	23	Pieces	\$ 0.58	\$	160.63
Resilient Channel RC PLUS - 25 GA	12	18	Pieces	\$ 0.30	\$	65.66
Resilient Channel RC PLUS - 25 GA	12	1984	Pieces	\$ 0.30	\$	7,237.30
Total					\$	42,076.90

Drywall Boards

Materials	Quantity	Units	Unit Price per (LF)		Total
16mm (5/8") TYPE X Gypsum Board	166180.35	SF	\$ 0.54	\$	88,906.49
2 Layer - 16mm (5/8") TYPE X Gypsum Board	163869.3	SF	\$ 0.54	\$	87,670.08
25mm (1") Gypsum board shaft linear panel	1024.8	SF	\$ 1.95	\$	1,999.38
Tile backer board	8892.45	SF	\$ 1.75	\$	15,561.79
16mm (5/8") Gypsum Board	210	SF	\$ 0.54	\$	113.40
13mm (1/2") Densglass Sheathing	1261.05	SF	\$ 1.16	\$	1,459.03
Level 4 Taping	254151.45	SF	\$ 0.13	\$	33,039.69
Total					\$ 228,749.86

Fire & Acoustic caulking

Materials	Quantity	Units	Unit Price per (LF)		Total
-----------	----------	-------	------------------------	--	-------

Fire caulking Single side of wall	3661	LF	\$ -	\$ -
Fire caulking Both side of wall	3767	LF	\$ -	\$ -
Acoustic caulking Single side of wall	315	LF	\$ -	\$ -
Acoustic caulking Both side of wall	4729	LF	\$ -	\$ -
Total				\$ -

Insulation

Material	Height	Quantity	Units	Unit Price per (LF)	Total
152mm (6") Acoustic Insulation - Fiberglass Batt		1570	SF	\$ 0.55	\$ 860.22
64mm (2 1/2") Acoustic Insulation -Fiberglass Batt		9117	SF	\$ 0.27	\$ 2,434.28
92mm (3 5/8") Acoustic Insulation - Fiberglass Batt		58672	SF	\$ 0.34	\$ 19,772.43
mineral wool rockwool insulation afb 6"		45315	SF	\$ 2.75	\$ 124,757.45
6mil Vapour Barrier		35872	SF	\$ 0.06	\$ 2,152.33
R16 batt insulation		5441	SF	\$ 0.54	\$ 2,910.99
MIN. 24 2-lb CLOSED CELL MEDIUM DENSITY SPRAY POLYURETHANE FOAM		2906	SF	\$ -	\$ -
R20 (5") spray fibre insulation - non-combustibl		11452	SF	\$ -	\$ -
Total					\$ 152,887.70

FASTENER

Material	ea	Box	Units	Unit Price Box	Total
#6 x 1-1/4" Drywall screws (Single Layer Drywall) - 8000 Pic/box	238339	30	Box	\$ 66.00	\$ 1,966.29
#6 x 1-5/8" Drywall screws (Double Layer Drywall) - 5000 Pic/box	36725	7	Box	\$ 66.00	\$ 484.77
#6 x 1-5/8" Self-drilling drywall screws (Ceiling Drywall) - 1000 Pic/box	79092	8	Box	\$ 150.00	\$ 1,186.39
#8 x 2" Self-drilling combo drive screws (Sheathing to Metal Studs) - 5000 Pic/box	1892	0	Box	\$ 108.50	\$ 41.05
Powder actuated pins or concrete screws (Track Installation) - 1000 Pic/box	14816	15	Box	\$ 250.00	\$ 3,703.93
#10 x 3/4" Self-drilling framing screws (Metal Stud Wall) - 8000 Pic/box	15351	2	Box	\$ 130.00	\$ 249.45
Total					\$ 7,631.88

Labour Cost

Material	Qty	Units	Unit Price	Total
One layer Drywall Board installation cost	176308	SF	\$ 0.28	\$ 49,366.13
Double layer Drywall Board installation cost	81935	SF	\$ 0.56	\$ 45,883.40
Exterior Sheathing installation cost	1261	SF	\$ 0.60	\$ 756.63
Interior wall Steel Framing Installation Cost up to 10'	312	LF	\$ 4.00	\$ 1,248.00
Interior wall Steel Framing Installation Cost up to 15'	267	LF	\$ 7.50	\$ 2,002.50
Exterior wall Steel Framing Installation Cost up to 10'	226	LF	\$ 11.00	\$ 2,486.00
Exterior wall Steel Framing Installation Cost up to 15'	12	LF	\$ 17.00	\$ 204.00
Resilient Channel RC PLUS - 25 GA - 12'	2002	Pieces	\$ 2.50	\$ 5,004.77
Duct Chase Labour Cost	1303	LF	\$ 2.60	\$ 3,387.80
Wall Insulation Installation Cost	83070	SF	\$ 0.35	\$ 29,074.40
Ceiling/floor Insulation Installation Cost	51404	SF	\$ 0.40	\$ 20,561.52
Stud GWB Ceiling Installation Cost	15032	SF	\$ 0.75	\$ 11,274.00
Bulkhead Installation cost Cost up to 2'	2081	LF	\$ 2.80	\$ 5,826.80
Level 4 Taping Labour Cost	254151	SF	\$ 0.38	\$ 96,577.55

Tapping tuchup after prime	64	Unit	<u>\$ 100.00</u>	<u>\$ 6,400.00</u>
Hollow Metal Door Frame Install only	54	EA	<u>\$ 40.00</u>	<u>\$ 2,160.00</u>
Caulking Single side of wall	3976	LF	<u>\$ -</u>	<u>\$ -</u>
Caulking Both side of wall	8496	LF	<u>\$ -</u>	<u>\$ -</u>
Total				<u>\$ 282,213.50</u>

CRTAGE

<u>Material</u>	<u>Qty</u>	<u>Units</u>	<u>Unit Price</u>	<u>Total</u>
CRTAGE-BOARD	341438	SF	0.06	<u>\$ 20,486.28</u>
CARTAGE- STEEL	92307	LF	0.009	<u>\$ 830.76</u>
CARTAGE INULATION	134474	SF	<u>0</u>	<u>\$ -</u>
Total				<u>\$ 21,317.04</u>

Total summary

<u>Material</u>	<u>Total</u>
Steel Fraimg Material Cost	<u>\$ 42,076.90</u>
Drywall Boards Material Cost	<u>\$ 228,749.86</u>
Fire & Acoustic caulking	<u>\$ -</u>
Act Ceiling Material Cost	<u>\$ -</u>
Specialty Ceilings/Items	<u>\$ -</u>
Insulation Material Cost	<u>\$ 152,887.70</u>
FASTENER	<u>\$ 7,631.88</u>
Toatel Labour Cost	<u>\$ 282,213.50</u>
Material Crtage	<u>\$ 21,317.04</u>
Grand without additional markups Total	<u>\$ 734,876.88</u>

Important Notes:-

A 5% consideration has been included in the estimate at the appropriate stage to account for general project variations.

For 2 Layer drywall board Quantity we have already multiply by 2

For caulking, please note that furring walls with gypsum board on only one side require caulking on one side, while walls with gypsum board on both sides require caulking on both sides. Please apply the pricing accordingly.

All wall heights have been rounded up to the nearest full foot to align with standard stud lengths, Example: A wall height of 9.7 ft is rounded up to 10 ft for material calculation.

We have included the Level 4 and Level 5 finish areas in the estimate based on the respective finish requirements. Please price them per square foot according to the amount of Tape roll, and mud box work needed for each finish type.